ELK GROVE

Phone: 916.683.7111

Fax: 916.691.3168

Web: www.elkgrovecity.org


Modification Number:


8401 Laguna Palms Way Elk Grove, California 95758

## **Modification or Addition to Improvement Standards and Details**

AR - 4.7

Effective Date of Change: 2/11/09		
Modification:		
1. Change 90" minimum on lower diagra above.	am to 72" minimum to be consisten	t with elevation
Effect of Modification:		
1. Correction to detail and consistency w	rith Standard Detail ST-20.	
	A.	
Request for Modification Initiated By:	Supervising Construction Inspecto	2.11.09 or Date
Modification Reviewed for Conformity and Consistency to Standards:	City Engineer	7(20\09 Date
Modification to Improvement Standards Approved:	Director of Public Works	7/20/09







## NOTES:

- A. DRIVEWAY WIDTH AS PER CITY CODE.
- B. WEAKENED PLANE JOINTS (WPJ) REQUIRED ON CENTERLINE FOR DRIVEWAYS 10' TO 20' WIDE. DRIVEWAYS 22' TO 35' WIDE SHALL HAVE TWO WPJ EVENLY SPACED AT 1/4 AND 1/4 POINTS.
- C. ALL CONSTRUCTION AND MATERIALS IN CONFORMANCE WITH SEC 27 AND 50 OF STANDARD SPECIFICATIONS.
- D. THICKNESS OF APRONS SHALL BE 4" ON RESIDENTIAL DRIVEWAYS AND 6" ON COMMERCIAL DRIVEWAYS. ON COMMERCIAL DRIVEWAYS SIDEWALK SHALL BE REMOVED AND REPLACED WITH 6" OF CONCRETE.
- E. THERE WILL BE A 48" X 48" LANDING AT THE TOP OF THE RAMP. THE 12" GROOVE BORDER WILL BE PART OF THE LANDING.

- F. APRON WILL BE DEPRESSED ON CURB AND GUTTER NO.13 WHEN RECONSTRUCTING EXISTING COMMERCIAL DRIVEWAYS.
- G. DETECTABLE WARNING SURFACE SHALL BE PLACED ON THE RAMP ON EACH SIDE OF THE DRIVEWAY APRON.
- H. DETECTABLE WARNING SURFACE SHALL BE PLACED 6" FROM THE APRON/RAMP WPJ.
- --- -- DESIGNATES THAT ELEMENT MAY BE CONSTRUCTED.
  - \* ON RECONSTRUCTION THE SLOPE CAN BE 10%.
  - \*\* IF CURB & GUTTER ARE POURED SEPARATE OF APRON THEN DOWELS ARE REQUIRED AT BACK OF CURB. 3" IN CURB AND 9" IN CENTER IF APRON.




DATE: 02/12/2007		7	NOT TO SCALE		CITY OF ELK GROVE - PUBLIC WORKS	APPROVED BY:		
REVISION	BY	APP	ROVED	DATE			CITY ENGINEER	
1	JP		RS	02/11/2009	SIDEWALK DRIVEWAY DETAIL			
							DRAWING NUMBER	
							AR - 4.7	



## NOTES:

- A. DRIVEWAY WIDTH AS PER CITY CODE.
- B. WEAKENED PLANE JOINTS (WPJ) REQUIRED ON CENTERLINE FOR DRIVEWAYS 10' TO 20' WIDE. DRIVEWAYS 22' TO 35' WIDE SHALL HAVE TWO WPJ EVENLY SPACED AT ½ AND ¾ POINTS.
- C. ALL CONSTRUCTION AND MATERIALS IN CONFORMANCE WITH SEC 27 AND 50 OF STANDARD SPECIFICATIONS.
- D. THICKNESS OF APRONS SHALL BE 4" ON RESIDENTIAL DRIVEWAYS AND 6" ON COMMERCIAL DRIVEWAYS. ON COMMERCIAL DRIVEWAYS SIDEWALK SHALL BE REMOVED AND REPLACED WITH 6" OF CONCRETE.
- E. THERE WILL BE A 48" X 48" LANDING AT THE TOP OF THE RAMP. THE 12" GROOVE BORDER WILL BE PART OF THE LANDING.

- F. DETECTABLE WARNING SURFACE SHALL BE PLACED ON THE RAMP ON EACH SIDE OF THE DRIVEWAY APRON.
- G. DETECTABLE WARNING SURFACE SHALL BE PLACED 6" FROM THE APRON/RAMP WPJ.
- -- DESIGNATES THAT ELEMENT MAY BE CONSTRUCTED.
  - \* ON RECONSTRUCTION THE SLOPE CAN BE 10%.
  - \*\* IF CURB & GUTTER ARE POURED SEPARATE OF APRON THEN DOWELS ARE REQUIRED AT BACK OF CURB. 3" IN CURB AND 9" IN CENTER IF APRON.



DATE: 02/12/2007		7	NOT TO SCALE		CITY OF ELK GROVE - PUBLIC WORKS	APPROVED BY:	
REVISION 1	BY		ROVED	DATE 02/11/2009		CITY ENGINEER	
'	31		110	02/11/2003	PLANTER STRIP DRIVEWAY DETAIL	CON ELK STOR	DRAWING NUMBER
						FIFORM	AR - 4.8