

Phone: 916.683.7111
Fax: 916.627.4400

www.elkgrovecity.org

PUBLIC WORKS
8401 Laguna Palms Way
Elk Grove, California 95758



Standards Update Transmittal

Reference Number: 2024-02
Standards: Standard Construction Specifications, 1-3; 49-1.04

Update:

1. Modification to Standard Construction Specifications:
 - a. Section 1-3 - DEFINITIONS, added “Authorized Materials List” (AML) and its definition to the section.
 - b. Section 49-1.04 – *Equipment List and Drawings*, revised to add reference to Authorized Materials List posted online.
2. Created a static web landing page for the AML on City of Elk Grove website.

Effect of Update:

1. This modification adds a definition of the term “Authorized Materials List” as it is referenced in our Standard Construction Specifications and a link to the list on the City webpage.
2. Currently we only have an authorized list of materials for Traffic Signals and Cabinets. This adds a reference to the Authorized Materials List (AML) and provides a link to the AML webpage.

Request for Update Initiated By: Shoaib Ahrary, PE, ESD Manager 3/22/2022

Update Reviewed for Conformity and Consistency to Standards:

Shoaib Ahrary 2/14/2024 | 3:24 PM PST
Shoaib Ahrary, PE, ESD Manager Date

Update to Standards Approved:

Jeffrey R. Werner 2/14/2024 | 6:26 PM PST
Jeffrey R. Werner, PE, City Engineer Date

49-1.04 Equipment List and Drawings

If requested by the City, the Contractor shall submit for review sample articles of the material proposed for use. After review, said sample articles will be returned. The Contractor shall include on the equipment list the installation location of material supplied. This shall be done by the use of street names, the alphabetical letter designation used on the Plans, or a location as otherwise noted on the Plans.

The equipment and materials proposed for use on any project shall be listed on the City's Authorized Materials List and approved by the Engineer before starting work.

In conformance with the requirements in Section 11-3, "As Built Drawings", of these Specifications, the Contractor shall maintain "As Built" plans that shall show in detail the construction changes of all traffic signal and streetlight wiring, conduits, standards, and associated equipment. In particular, the "As Built" plans shall accurately depict the location and depth of conduits, location of standards, pull boxes, wiring changes, and all applicable manufacturer's operation and maintenance information.